


VISIONING - TOWER



- SCHEDULE
- 1- Extension of tower leg at terminating vista at corner plaza
 - 2- Composition of clean volumes with stucco and control joints
 - 3- Use of extended exoskeleton to provide facade with dimension and shadow play
 - 4- Office like facade enhanced by glazing at base and playful panel and glazing at linear levels
 - 5- Modern arbor canopy at pool deck



VISIONING - GARAGE



- SCHEDULE
- 1- Louvered design alternating louver direction at garage
 - 2- Perforated metal panels at garge with punched openings
 - 3- Trellis element at pool deck level
 - 4- Metal panel stair enclosure to enhance visibility and illuminate day and night

Revision Schedule		
Rev. #	Revision Description	Date

Revision Schedule		
Rev. #	Revision Description	Date

PROJECT NAME:
NORTH MIAMI BEACH
APARTMENTS

PROJECT ADDRESS:
359 NE 164TH ST, NORTH
MIAMI BEACH, FL 33162


PROJECT NO.:
2006













**P&Z AND CITY
COMMISSION
REVIEW**

12/10/2021

HEET NAME
OUTH ELEVATION

SHEET NO.
A-201















1 Elevation South		3/64" = 1'-0"			
	1 Simply White BM - OC-117 for body of building and grid.LRV: 91.7		5 Aluminum trellis at ground floor retail/office in bronze color	 	9 Perforated metal panels in whitesnip at the garage
	2 White Dove for accent color on building - OC-17.LRV: 85.38		6 Aluminum metal screen at crown of tower in white		
	3 Window glass clear with light tint. (glass is not mirror type and shall permit view of activities inside)		7 Railing - brushed aluminum supports with brushed aluminum perforated metal panels		10 Prodema at the soffit at the amenity deck
	4 Aluminum window frame in white – typical throughout building (unit apartment and retail/office storefront)		8 Louvered panels in bronze at the garage		11 Panel at Entry to receive Art Work



**NOT FOR
CONSTRUCTION**

SHEET NO.



A-202



1 Elevation North							
A-202 3/84" = 1'-0"							
	1 Simply White BM - OC-117 for body of building and grid.LRV: 91.7		5 Aluminum trellis at ground floor retail/office in bronze color		9 Perforated metal panels in whitesnip at the garage		
	2 Mustang for accent color on building - 2111-30. LRV: 8.95		6 Aluminum metal screen at crown of tower in white		10 Prodema at the soffit at the amenity deck		
	3 Window glass clear with light tint. (glass is not mirror type and shall permit view of activities inside)		7 Railing - brushed aluminum supports with brushed aluminum perforated metal panels		11 Panel at Entry to receive Art Work		
	4 Aluminum window frame in white – typical throughout building (unit apartment and retail/office storefront)		8 Louvered panels in bronze at the garage				



1 EAST ELEVATION A-203 3/64" = 1'-0"		2 WEST ELEVATION A-203 3/64" = 1'-0"	
	1 Simply White BM - OC-117 for body of building and grid.LRV: 91.7		5 Aluminum trellis at ground floor retail/office in bronze color
	2 Mustang for accent color on building - 2111-30. LRV: 8.95		6 Aluminum metal screen at crown of tower in white
	3 Window glass clear with light tint. (glass is not mirror type and shall permit view of activities inside)		7 Railing - brushed aluminum supports with brushed aluminum perforated metal panels
	4 Aluminum window frame in white – typical throughout building (unit apartment and retail/office storefront)		8 Louvered panels in bronze at the garage
			9 Perforated metal panels in whitesnip at the garage
			10 Prodema at the soffit at the amenity deck
			11 Panel at Entry to receive Art Work




1 MOTOR COURT EAST VIEW
A-204 3/64" = 1'-0"

	1 Simply White BM - OC-117 for body of building and grid.LRV: 91.7
	2 Mustang for accent color on building - 2111-30. LRV: 8.95
	3 Window glass clear with light tint. (glass is not mirror type and shall permit view of activities inside)
	4 Aluminum window frame in white – typical throughout building (unit apartment and retail/office storefront)


	5 Aluminum trellis at ground floor retail/office in bronze color
	6 Aluminum metal screen at crown of tower in white
	7 Railing - brushed aluminum supports with brushed aluminum perforated metal panels
	8 Louvered panels in bronze at the garage

2 MOTOR COURT WEST VIEW
A-204 3/64" = 1'-0"


	9 Perforated metal panels in whitesnip at the garage
	10 Prodema at the soffit at the amenity deck
	11 Panel at Entry to receive Art Work




4 Perforated metal panels in whitesnip at the garage



1 LONGITUDINAL SECTION2
3/64" = 1'-0"



1
Aluminum metal screen at
crown of tower in white




2
Railing - brushed aluminum
supports with brushed alum.
perforated metal panels




3
Louvered panels in
bronze at the garage



4
Perforated metal panels
in whitesnip at the garage



1 EAST TOWER SECTION
A-302 3/64" = 1'-0"



1
Aluminum metal screen at
crown of tower in white




2
Railing - brushed aluminum
supports with brushed alum.
perforated metal panels




3
Louvered panels in
bronze at the garage



4
Perforated metal panels
in whitesnipe at the garage




2 EAST TOWER SECTION1
A-302 3/64" = 1'-0"




2 WEST TOWER SECTION1
A-303 3/64" = 1'-0"




1 Aluminum metal screen at crown of tower in white




2 Railing - brushed aluminum supports with brushed aluminum perforated metal panels



1 WEST TOWER SECTION
A-303 3/64" = 1'-0"



3 Louvered panels in bronze at the garage



4 Perforated metal panels in whitesnip at the garage



1 PERSPECTIVE - NE 19TH AV. CORNER LOOKING NORH
A-900



2 PERSPECTIVE - NE 19TH AV. LOOKING SOUTH
A-900



3 AERIAL PERSPECTIVE - NE 19TH AV. CORNER LOOKING NORTH
A-900



4 PEDESTRIAN CORNER VIEW FROM NE 19TH AV. & NE 164TH STREET
A-900



5 PEDESTRIAN VIEW TO THE MOTOR COURT FROM NE 164TH STREET
A-900




6 PEDESTRIAN CORNER VIEW FROM NE 20TH AV. & NE 164TH STREET
A-900



1 PEDESTRIAN VIEW - NE 20TH AV. LOOKING SOUTH



2 AERIAL PERSPECTIVE LOOKING EAST TOWER AMENITY DECK



3 PEDESTRIAN VIEW TO MOTOR COURT FROM ALLEY



4 AERIAL PERSPECTIVE LOOKING TO THE WEST TOWER CROWN



5 PEDESTRIAN VIEW TO THE OFFICE BUILDING



6 AERIAL PERSPECTIVE LOOKING WEST TOWER AMENITY DECK

**NOT FOR
CONSTRUCTION**

Revision Schedule		
Rev. #	Revision Description	Date

PROJECT NAME:
NORTH MIAMI BEACH
APARTMENTS
PROJECT ADDRESS:
1959 NE 164TH ST, NORTH
MIAMI BEACH, FL 33162
PROJECT NO.:
02006
**P&Z AND CITY
COMMISSION
REVIEW**
12/10/2021

SHEET NAME
PERSPECTIVES



CLIENT:

GFS CORP.

**NOT FOR
CONSTRUCTION**

Revision Schedule		
Rev. #	Revision Description	Date

PROJECT NAME:
NORTH MIAMI BEACH
APARTMENTS
PROJECT ADDRESS:
1959 NE 164TH ST, NORTH
MIAMI BEACH, FL 33162
PROJECT NO.:
02006
**P&Z AND CITY
COMMISSION
REVIEW**
12/10/2021

SHEET NAME
RENDERING - STREET
VIEW PERSPECTIVE

SHEET NO.

A-902



**NOT FOR
CONSTRUCTION**

Revision Schedule		
Rev. #	Revision Description	Date

PROJECT NAME:
NORTH MIAMI BEACH
APARTMENTS
PROJECT ADDRESS:
1959 NE 164TH ST, NORTH
MIAMI BEACH, FL 33162
PROJECT NO.:
02006
**P&Z AND CITY
COMMISSION
REVIEW**
12/10/2021

SHEET NAME
RENDERING - SOUTH
AERIAL VIEW

SHEET NO.
A-903



**NOT FOR
CONSTRUCTION**

Revision Schedule		
Rev. #	Revision Description	Date


PROJECT NAME:
NORTH MIAMI BEACH
APARTMENTS
PROJECT ADDRESS:
1959 NE 164TH ST, NORTH
MIAMI BEACH, FL 33162
PROJECT NO.:
02006
**P&Z AND CITY
COMMISSION
REVIEW**
12/10/2021

SHEET NAME
RENDERING -
PEDESTRIAN VIEW
PERSPECTIVE

SHEET NO.
A-904



LOCATION MAP



SITE SYMBOLS LEGEND

- PROPOSED STOP SIGN (R1-1)
- PROPOSED PARKING SPACE
- EXISTING PARKING SPACE
- EXISTING STOP SIGN (R1-1)
- PROPOSED ONE WAY SIGN (R6-1)
- EXISTING LIGHT POLES


SITE DATA

1. TOTAL SITE AREA = 1.86 AC

PAVEMENT LEGEND

- PROPOSED HEAVY DUTY CONCRETE PAVEMENT
(REFER TO LANDSCAPE PLANS FOR PATTERN)
- PROPOSED SIDEWALK PAVEMENT
(REFER TO LANDSCAPE PLANS FOR PATTERN)
- PROPOSED HEAVY DUTY ASPHALT PAVEMENT
- PROPOSED GREEN AREA

NOTE:
REFER TO LANDSCAPE PLANS FOR
VISION CLEARANCE TRIANGLES



**NOT FOR
CONSTRUCTION**

Revision Schedule

Rev. #	Revision Description	Date
--------	----------------------	------

PROJECT NAME:
NORTH MIAMI BEACH
APARTMENTS

PROJECT ADDRESS:
1959 NE 164TH ST, NORTH
MIAMI BEACH, FL 33162

PROJECT NO.:
02006


**P&Z AND CITY
COMMISSION
REVIEW**
12/10/2021


SHEET NAME

SCHEMATIC SITE
DIMENSION PLAN

SHEET NO.


C-1





NUMBER	SCIENTIFIC NAME	COMMON NAME	CONDITION	DISPOSITION	TRUNK CALIPER (FT.)	HEIGHT (FT.)	SPREAD (FT.)	COMMENTS	AREA OF CANOPY REMOVED (SQ. FT.)
1	Quercus virginiana	Live Oak	FAIR	REMOVE	1	25	25	NATIVE	490.63
2	Quercus virginiana	Live Oak	FAIR	REMOVE	1	25	20	NATIVE	314.00
3	Adonidia memilii	Christmas Palm Triple	FAIR	REMOVE	0.5	18	12	NON-NATIVE	113.04
4	Quercus virginiana	Live Oak	POOR	REMOVE	0.9	20	18	NATIVE	254.34
5	Quercus virginiana	Live Oak	FAIR	REMOVE	0.8	25	20	NATIVE	314.00
6	Quercus virginiana	Live Oak	FAIR	REMOVE	0.9	28	20	NATIVE	314.00
7	Quercus virginiana	Live Oak	POOR	REMAIN	0.8	20	18	NATIVE	
8	Sabal Palmetto	Cabbage Palm	FAIR	REMOVE	1	22	12	NATIVE	113.04
9	Sabal Palmetto	Cabbage Palm	FAIR	REMOVE	1	18	12	NATIVE	113.04
10	Sabal Palmetto	Cabbage Palm	FAIR	REMOVE	1	22	12	NATIVE	113.04
11	Ptychosperma elegans	Alexander Palm Triple	POOR	REMOVE	0.6	14	10	NON-NATIVE	78.50
12	Quercus virginiana	Live Oak	FAIR	REMAIN	0.7	20	20	NATIVE	
13	Quercus virginiana	Live Oak	FAIR	REMAIN	0.9	25	20	NATIVE	
14	Quercus virginiana	Live Oak	POOR	REMAIN	0.9	25	18	NATIVE	
15	Quercus virginiana	Live Oak	FAIR	REMOVE	0.9	25	20	NATIVE	314.00
16	Quercus virginiana	Live Oak	FAIR	REMOVE	0.8	27	20	NATIVE	314.00
17	Quercus virginiana	Live Oak	FAIR	REMOVE	1	25	20	NATIVE	314.00
18	Quercus virginiana	Live Oak	FAIR	REMAIN	0.9	25	20	NATIVE	
19	Quercus virginiana	Live Oak	FAIR	REMAIN	1	25	20	NATIVE	
20	Ptychosperma elegans	Alexander Palm	FAIR	REMOVE	0.6	27	10	NON-NATIVE	78.50
21	Ptychosperma elegans	Alexander Palm Double	POOR	REMOVE	0.6	14	8	NON-NATIVE	50.24
22	Ptychosperma elegans	Alexander Palm Double	POOR	REMOVE	0.6	14	8	NON-NATIVE	50.24
23	Quercus virginiana	Live Oak	FAIR	REMOVE	1	22	20	NATIVE	314.00
24	Quercus virginiana	Live Oak	POOR	REMOVE	0.9	20	20	NATIVE	314.00
25	Quercus virginiana	Live Oak	POOR	REMOVE	0.7	20	18	NATIVE	254.34
26	Quercus virginiana	Live Oak	FAIR	REMOVE	1	25	20	NATIVE	314.00
27	Adonidia memilii	Christmas Palm Double	FAIR	REMOVE	0.5	12	10	NON NATIVE	78.50
28	Adonidia memilii	Christmas Palm Triple	FAIR	REMOVE	0.5	10	10	NON NATIVE	78.50
29	Adonidia memilii	Christmas Palm Triple	FAIR	REMOVE	0.5	15	10	NON NATIVE	78.50
30	Adonidia memilii	Christmas Palm Double	FAIR	REMOVE	0.5	15	10	NON NATIVE	78.50
CANOPY BEING REMOVED (IN SQUARE FEET)									4,848.95
MITIGATION TREES REQUIRED: 1 SHADE TREE @ 12' HIGH / 500 SF OF CANOPY REMOVED						4,534.95 SF	/ 500 SF =		10 TREES
TREES PROVIDED TOWARDS MITIGATION REQUIREMENTS (SEE LA-01)									★10 TREES

★MITIGATION TREES WILL BE PROVIDED OFF SITE AT A LOCATION AGREED UPON WITH THE CITY STAFF



SITE LEGEND	
LINE TYPE	DEFINITION
---	EXISTING FEATURES
---	PROPOSED SITE FEATURES
■	PROPOSED BUILDING

TREE DISPOSITION LEGEND	
SYMBOL	ACTION
⊗ #	TO BE REMOVED
⊗ #	TO BE RELOCATED
⊙ #	TO REMAIN AND BE PROTECTED

CLIENT:

GFS CORP.

NOT FOR
CONSTRUCTION

KIRK OLNEY FL LA LICENSE No.: 00001705

Revision Schedule		
Rev. #	Revision Description	Date

PROJECT NAME:
NORTH MIAMI BEACH
APARTMENTS
PROJECT ADDRESS:
NE 164TH ST & 19TH AVE,
NORTH MIAMI BEACH, FL 33162
PROJECT NO.:
02006

P & Z AND CITY
COMMISSION
REVIEW
12/10/2021

SHEET NAME
TREE DISPOSITION
PLAN & TABLE

SHEET NO.

LT-01

PART 1 - GENERAL
FOR SIMPLIFICATIONS, THE TERM 'TREES/S' IS USED TO REFER TO ALL PLANT MATERIAL TO BE RELOCATED. ALSO, 'CROWN' DOES NOT REFER TO PALMS UNLESS STATED OTHERWISE ON THE DRAWINGS.

1.01 RELATED WORK (NOT APPLICABLE)

1.02 DESCRIPTION OF WORK

PROVIDE LABOR, MATERIALS, EQUIPMENT AND SERVICES TO COMPLETE THE TREE/PALM RELOCATION WORK, AS INDICATED ON THE DRAWINGS, AS SPECIFIED HEREIN, OR BOTH.

- A. INCLUDE THE FOLLOWING:
1. PREPARATION OF TREES FOR RELOCATION.
 2. PRUNE CANOPIES AS NECESSARY OR AS DIRECTED BY AN ISA APPROVED ARBORIST.
 3. ROOT PRUNING AND HARDENING OFF.
 3. RELOCATE TREES AS SHOWN ON THE PLANS AND BACKFILL HOLES WITH PLANTING SOIL.
 4. STAKE OR OTHERWISE BRACE RELOCATED TREES AS SHOWN ON THE DRAWINGS.
 5. ERECT PROTECTIVE BARRIERS BEFORE AND AFTER RELOCATION.
 6. PROVIDE CONTINUOUS IRRIGATION.
 7. FERTILIZE, SPRAY, PRUNE, AND MAINTAIN IN HEALTHY CONDITION UNTIL FINAL ACCEPTANCE.
 8. FILL TREE PITS AT OLD LOCATIONS OF TREES WITH PLANTING SOIL MIXTURE AND SOD THE AREA.

1.03 QUALITY ASSURANCE

- A. THE SUPERVISORS USED FOR TRANSPLANTING EXISTING SHRUBS, TREES, AND OR PALMS SHALL HAVE A MINIMUM OF FIVE (5) YEARS EXPERIENCE IN THE FIELD OF RELOCATION OF SIMILAR TYPE PLANT MATERIALS AND SHALL BE A MEMBER OF THE AMERICAN ASSOCIATION OF NURSERYMEN.
- B. ENGAGE AND OR RETAIN THE SERVICES OF A CERTIFIED MEMBER OF THE AMERICAN SOCIETY OF CONSULTING ARBORISTS (ISA) TO OBSERVE, MONITOR, AND DIRECT ALL TREE RELOCATION PROCEDURES. INTERNATIONAL SOCIETY OF ARBORICULTURE (ISA) MEMBERSHIP/CREDENTIALS' ONLY, IS NOT SUFFICIENT FOR THE REQUIREMENTS OF THIS PROJECT. ISA MEMBER MUST BE PRESENT FOR ALL RELOCATION PROCEDURES. A WEEKLY INSPECTION MUST BE CONDUCTED BY THE ISA MEMBER AFTER RELOCATION IS COMPLETE TO EVALUATE THE GENERAL HEALTH OF TREES. A WRITTEN SUMMARY OF FINDINGS MUST BE PROVIDED TO THE OWNER'S REPRESENTATIVE WEEKLY DURING RELOCATION AND ESTABLISHMENT PERIOD.
- C. FOR NAMES AND LOCATIONS OF QUALIFIED ISA MEMBERS VISIT WWW.ISA-ARBOR.COM.
- D. PROTECTION OF EXISTING, TREES, SHRUBS, AND PALMS:
1. PROTECT WITH BARRICADES AS DETAILED ON THE DRAWINGS TO PREVENT ENCROACHMENT BENEATH CANOPIES.
 2. REPLACE EXISTING TREES OR SHRUBS THAT ARE DAMAGED, SCARRED, OR DESTROYED BY THE CONTRACTOR WITH SAME SPECIES, SIZE AND QUALITY.

1.04 SUBMITTALS

- A. SUBMIT A LIST OF EQUIPMENT, PROCEDURE, AND LABOR FORCE FOR USE IN TRANSPLANTING WORK.
- B. SUBMIT A DAILY RELOCATION SCHEDULE.
- C. SUBMIT MANUFACTURER'S LITERATURE ON WETTING AGENTS, FERTILIZERS, AND CONDITIONERS.
- D. ARBORIST MUST PROVIDE TO THE OWNER'S REPRESENTATIVE WEEKLY REPORTS WHICH SHALL INCLUDE:
1. SUMMARY OF SITE ACTIVITIES AND CONDITIONS RELATING TO ALL TREES ONSITE.
 2. EVALUATION OF EACH TREE'S CONDITION.
 3. RECOMMENDATIONS ON WHAT SHOULD BE DONE TO IMPROVE SURVIVABILITY OF RELOCATED TREES.

1.05 EXISTING CONDITIONS

- A. NO REPRESENTATIONS ARE MADE AS TO SUBSURFACE CONDITIONS.
- B. CONTRACTOR MUST FIELD VERIFY THE LOCATION OF ALL EXISTING UTILITIES, STRUCTURES AND PLANT MATERIAL.

PART 2 - PRODUCTS

2.01 FERTILIZER

- A. FERTILIZER MIX:
1. A MIXTURE OF UREAFORM AMMONIUM PHOSPHATE AND SOLUBLE POTASH SUSPENDABLE POWDER TO BE DILUTED IN WATER AT A RATE OF 40 POUNDS OF FERTILIZER PER 100 GALLONS OF WATER.
 2. USE FORMULA 30410 WITH 50% NITROGEN IMMEDIATELY AVAILABLE FOR RELEASE AND 50% SLOW RELEASE OVER TWELVE MONTHS.
 3. PRODUCT: USE ARBORGREEN AS MANUFACTURED BY LESCO, INC. OR AN APPROVED EQUAL.
- B. WETTING AGENT:
1. LESCO WET AS MANUFACTURED BY LESCO, INC. OR AN APPROVED EQUAL.
 2. DILUTE AT A RATE RECOMMENDED BY THE MANUFACTURER.
- C. MINOR ELEMENT:
1. MICRO MIX LIQUID AS PRODUCED BY LESCO, INC. OR AN APPROVED EQUAL.
 2. DILUTE IN WATER AT A RATE RECOMMENDED BY THE MANUFACTURER.
- D. TIME RELEASE FERTILIZER TABLETS: AGRIFORM, 15 GRAM, DESIGNATION 20-10-5, OR APPROVED EQUAL.
- E. USE THE FOLLOWING MIXTURE FOR DEEP ROOT FERTILIZER FOR TRANSPLANTED SHRUBS, TREES, AND PALMS:
- 1/3 LIQUID FERTILIZER MIX
1/3 WETTING AGENT MIX
1/3 MINOR ELEMENT MIX
- USE INJECTION EQUIPMENT THAT AGITATES THE MIXTURE FOR UNIFORMITY OF APPLICATION.

2.02 SOIL BACKFILL/PLANTING SOIL MIX

- A. PLANTING SOIL MIX:
1. SOIL USED FOR PLANTING SHALL BE FREE FROM STICKS, ROOTS, STONES, OR OTHER EXTRANEIOUS MATERIAL DETRIMENTAL OR INJURIOUS TO PLANTS. PARTICULAR CARE SHOULD BE TAKEN TO REMOVE PIECES OF MORTAR, CEMENT, WOOD, AND OTHER SIMILAR REMAINS OF CONSTRUCTION FROM ALL PLANTING AREAS.
 2. SOIL USED FOR PLANTING MIX SHALL BE 50% EXISTING/SURROUNDING SOIL AND 50% IMPORTED (CONSISTING OF 1/3 APPROVED SOIL BACKFILL, 1/3 FLORIDA PEAT, AND 1/3 CLEAN D.O.T. SAND).
 3. "ACCEPTABLE SOIL BACKFILL" AND ANY IMPORTED SOIL USED ON THE PROJECT SHALL BE A NATURAL, FERTILE, FRIABLE SOIL POSSESSING CHARACTERISTICS REPRESENTATIVE OF A WELL-DRAINED AREA IN FLORIDA. SOIL CONTAINING MUCK OR POORLY DRAINED SOILS SHALL NOT BE USED.
 4. PRIOR TO INSTALLATION OF PLANT MATERIAL IN PLANTERS (AREAS SUCH AS ROADWAY MEDIANS THAT ARE SURROUNDED BY CONCRETE OR PAVEMENT), ALL MATERIAL (INCLUDING BUT NOT LIMITED TO COMPACTED EARTH, ROAD ROCK OR CONSTRUCTION DEBRIS) SHALL BE REMOVED TO A MINIMUM DEPTH OF 3'-0" AND BACKFILLED WITH SOIL BACKFILL.

2.03 BRACING AND STAKING

- A. STAKE OR OTHERWISE BRACE RELOCATED TREES/PALMS AS SHOWN ON THE DRAWINGS (LL-03)
- B. WRAP TRUNK WITH THREE LAYERS OF BURLAP
- C. ATTACHED BATTENS TO TRUNK WITH TWO METAL STRAPS.
- D. ALL BRACES SHALL BE ATTACHED AT THE GROUND WITH STAKES AS SHOWN ON LL-03
- E. PROVIDE 2" X 4" PRESSURE TREATED WOOD BRACES FOR TREES/PALMS UP TO 6" CALIPER
- F. PROVIDE 4" X 4" PRESSURE TREATED WOOD BRACES FOR TREES/PALMS OVER 8" CALIPER
- G. PROVIDE THE NUMBER OF MEMBER BRACES PER TREE AS FOLLOWS:
- | CALIPER | NUMBER OF PRESSURE TREATED BRACES |
|-----------|-----------------------------------|
| UP TO 4" | THREE BRACES |
| 4" TO 8" | FOUR BRACES |
| 8" AND UP | FIVE BRACES |
- ALL BRACING SHALL BE ATTACHED TO STAKE AND BATTENS WITH GALVANIZED WOOD SCREWS.

2.04 WATER

- A. FREE OF SUBSTANCES HARMFUL TO PLANT GROWTH, OBJECTIONABLE ODOR OR STAINING AGENTS.
- B. THE WATER USED FOR ESTABLISHMENT OF PLANT MATERIAL SHALL BE CLEAN AND FREE OF DIRT, DEBRIS, POISONS, PESTICIDES, CONTAMINANTS AND ANY OTHER MATERIAL OR COMPOUND THAT IS DETRIMENTAL OR INHIBITS VIGOROUS PLANT GROWTH
- C. PROVIDED BY THE CONTRACTOR AND OBTAINED FROM ITS SOURCE LEGALLY. WATER DRAWN FROM CANALS AND OR LAKES AND ACCESS THEREOF WILL BE DONE ONLY WITH THE EXPRESS WRITTEN APPROVAL OF THE OWNER OF SAID PROPERTY AND OR APPLICABLE FEDERAL, STATE AND LOCAL LAWS, REGULATIONS, STANDARDS OR OTHER REGULATORY REQUIREMENTS.
- D. CONTRACTOR SHALL ROUTINELY AND REGULARLY PROVIDE SUFFICIENT SUPPLEMENTAL WATER TO RELOCATED AND EXISTING TREES IMPACTED BY CONSTRUCTION ACTIVITIES, AS WELL AS RELOCATED TREES, TO PROVIDE FOR VIGOROUS PLANT HEALTH AND GROWTH.

PART 3 - EXECUTION

3.01 GENERAL PREPARATION

- A. CONTRACTOR TO VERIFY THAT TREES IN THE FIELD MATCH TREES DESIGNATED ON THE DRAWINGS. OBTAIN CONCURRENCE OF THE OWNER'S REPRESENTATIVE PRIOR TO CROWN PRUNING.
- B. REMOVE TREES, SAPLINGS, SHRUBS, BUSHES, VINES AND UNDERGROWTH THAT INTERFERE WITH RELOCATION. HAND-CLEARING ONLY IS PERMITTED WITHIN THE DRIP-LINE OF TREES TO BE RELOCATED.
- C. CLEAR THE ROOT BALL AREA BY HAND ONLY OF FOREIGN MATERIAL AND TRASH TO EXPOSE UNDISTURBED SOIL.
- D. VERIFY PERCOLATION RATES AND SOIL'S ACCEPTABILITY AT LOCATIONS TO WHICH THE TREES ARE TO BE TRANSPLANTED.
- E. ALL TREES SHALL BE PRE-TIED IN OR TIED BACK TO PREVENT BREAKAGE AND SCRAPING OF LIMBS IN ORDER TO FACILITATE MACHINERY MOVEMENT

3.02 PREPARATION PRIOR TO RELOCATION

- A. IN THE PRESENCE AND DIRECTION OF ISA MEMBER, PERFORM CROWN PRUNING BETWEEN 30 AND 60 DAYS PRIOR TO TRANSPLANTING.
- B. ALL TREES SHALL BE PRE-PRUNED USING CLASS 4 SPECIFICATIONS
- C. FERTILIZATION AND WATERING:
1. INJECT THE FERTILIZER MIXTURE INTO THE SOIL WITHIN 24 HOURS AFTER CROWN PRUNING, AND AT A MINIMUM OF 14 DAYS PRIOR TO RELOCATION.
 2. INJECT THE DEEP ROOT FERTILIZER MIXTURE AT A RATE RECOMMENDED BY THE MANUFACTURER INTO THE ROOT ZONES OF SHRUBS, TREES, AND PALMS TO BE RELOCATED.
 3. ALL TREES SHOULD BE WATERED IN THE FIELD PRIOR TO TRANSPLANTING USING A MINIMUM OF 50 GALLONS PER TREE.
 4. WATER IS TO BE PROVIDED BY THE CONTRACTOR AND OBTAINED LEGALLY.
- D. CROWN PRUNING:
1. TRIM TREES TO BE RELOCATED BY THINNING THE CROWN ONLY, AND NOT BY REDUCING CROWN DIMENSIONS. TRIM TO CONFORM TO ANSI A300 AND IFAS CIR853 STANDARDS, INCLUDING REMOVAL OF DEAD WOOD. REPAIR INJURIES TO TREES INCLUDING CAVITIES AND MACHINERY MARKS.
 2. REMOVE SEEDPODS FROM SABAL PALMS, AND ALL BUT TEN OF THE YOUNGEST FRONDS. TRIM BOOTS TO A CLEAN, REGULAR PATTERN.
 3. REMOVE TRIMMINGS OFF-SITE AND DISPOSE OF IN ACCORDANCE WITH THE CITY CODE.
 4. UNDER NO CIRCUMSTANCE SHALL MORE THAN 30% OF THE CANOPY BE REMOVED.

- E. ROOT PRUNING
1. PERFORM ROUGH PRUNING AT NO LESS THAN HALF THE DISTANCE BETWEEN THE DRIP LINE AND THE TRUNK
 2. PROVIDE TEN INCHES (10") OF ROOT BALL DIAMETER FOR EVERY 1" OF TRUNK CALIPER (MEASURED AT 12" ABOVE EXISTING GRADE).
 3. MINIMUM BALL DEPTH FOR BROADLEAF TREES: BALL DIAMETER MINIMUM DEPTH 36" - 48" 60% OF DIAMETER 48" AND UP 35" MINIMUM
 4. LEAVE ROOTS WITH A SMOOTH, CLEAN CUT WITHOUT TEARS OR SPLITS.
 5. TREES TO BE RELOCATED WITH A CALIPER IN EXCESS OF TWELVE INCHES (12") SHALL BE ROOT PRUNED BY HAND.
 6. PRIOR TO TRANSPLANTING, PRUNE ROOT SYSTEM IN THIRDS, 8 WEEKS APART.
 7. BACKFILL TRENCH WITH SUGAR SAND.
- F. IRRIGATION AND WATER
1. PROVIDE A MINIMUM OF THREE TIMES PER WEEK HAND WATERING OF EACH TRANSPLANTED TREE. RATE OF WATER APPLICATION SHALL BE: A MINIMUM OF 20 GALLONS OF WATER PER INCH OF CALIPER PER APPLICATION.
- G. PROTECTION:
1. ERECT TREE PROTECTION MEASURES AS SHOWN ON THE DRAWINGS TO PROTECT INDIVIDUAL OR GROUPS OF TREES TO BE TRANSPLANTED.

3.03 RELOCATION

- A. GENERAL
1. VERIFY THE PRESENCE OF VIGOROUS FEEDER ROOTS PRIOR TO RELOCATION OPERATIONS.
 2. INJECT DEEP-ROOT FERTILIZER MIXTURE INTO THE SOIL 14 DAYS PRIOR TO TRANSPLANTING. APPLY AT A RATE RECOMMENDED BY THE MANUFACTURER INTO ROOT ZONES OF TREES AND PALMS.
 3. SOAK TREE BALLS TO THE FULL DEPTH DAILY FOR SEVEN CONSECUTIVE DAYS PRIOR TO RELOCATING.
 4. LOCATE POSITION AND ELEVATION WHERE TREES ARE INTENDED TO BE PLANTED FOR VERIFICATION BY OWNER'S REPRESENTATIVE.
 5. SELECT A MOVING ROUTE WHERE OVERHEAD AND UNDERGROUND UTILITIES, EXISTING OR PROPOSED, DO NOT CONFLICT WITH THE TRANSPLANTING PROCESS. COORDINATE THE ROUTE AND MOVING SCHEDULE WITH THE OWNER'S REPRESENTATIVE AND OTHER TRADES.
 6. NOTIFY THE OWNER'S REPRESENTATIVE 24 HOURS IN ADVANCE OF EACH RELOCATION TO ALLOW FOR OBSERVATION OF PROCEDURES.
- B. EQUIPMENT
1. A 65" TRANSPLANTING MACHINE WILL BE SUFFICIENT FOR TREES UP TO 4" CALIPER BUT NO LARGER.
 2. A BIG JOHN MODEL 90 MACHINE WILL BE SUFFICIENT FOR TREES UP TO 8" IN CALIPER
 3. A 102" MACHINE WILL BE SUFFICIENT FOR TREES 9" - 12" IN CALIPER
 4. HAND DIGGING (BALL AND BURLAP) IS ACCEPTABLE AND MAY BE USED AT THE DISCRETION OF THE ISA MEMBER.
 5. ALL CALIPERS ARE MEASURED AT 1 FT. ABOVE EXISTING GRADE.
 6. ALL TRANSPLANTING MACHINES WILL HAVE CLEAN, TIGHT-FITTING SHARP BLADES.
 7. ANY MACHINE DEEMED "LOOSE" BY THE ISA MEMBERS WILL BE REJECTED AS UNSATISFACTORY.
 8. TREES TO BE RELOCATED WITH A CALIPER IN EXCESS OF TWELVE INCHES (12") SHALL BE RELOCATED VIA TREE BOX OR OTHER APPROVED METHOD.
- C. DIGGING AND MOVING
1. DIG PITS A MINIMUM OF 42" DEEP WITH VERTICAL SIDES AND NET BOTTOM.
 2. HANDLE TREES TO AVOID DAMAGE TO BARK AND LIMBS. ATTACH SUPPORT STRAPS, CABLES, OR CHAINS AT MULTIPLE POINTS FOR WEIGHT DISTRIBUTION.
 3. DO NOT FORCE TREE FROM GROUND PRIOR TO UNDERCUTTING ROOT BALLS. DETERMINE FINAL BALL DEPTH UPON ASSESSING CONDITIONS AT TIME OF TRENCHING. NOTIFY OWNER'S REPRESENTATIVE IF BALL DEPTH VARIES FROM SPECIFIED DEPTH.
 4. SABAL PALMS MAY BE RELOCATED BY MEANS OF TREE SPADE AT THE DISCRETION OF THE CONTRACTOR. OTHERWISE, LIFT SIMILARLY TO CANOPY TREES.
 5. TREES ARE TO BE PLACED IN HEAVY GRADE BASKETS LINED WITH TWO LAYERS OF BURLAP FOR RELOCATION PROCEDURES OR PRIOR TO PLACEMENT IN HOLDING AREA (IF APPLICABLE).
 6. PLANT TOP OF ROOT BALLS THREE-INCHES (3") ABOVE FINISH GRADE.
 7. ALL TREES TRANSPLANTED IN ANY GIVEN DAY WILL BE WATERED IN, SANDED, MULCHED, AND UNTIED THAT SAME DAY.

- D. TREES IN HOLDING AREA (IF APPLICABLE)
1. LOCATE ROOT BALLS AS CLOSE TOGETHER WITHOUT DAMAGING THE CROWN OF THE TREE
 2. ALL TREES SHALL BE SET IN HOLES 3"-6" ABOVE EXISTING GRADE IN THE TREE HOLDING AREA.
 3. INSURE CLEARING AND GRUBBING IS COMPLETE IN HOLDING AREA
 4. IMMEDIATELY BACKFILL VOIDS BETWEEN ROOT BALLS AND WATER IN TO REMOVE AIR POCKETS.
 5. SOIL HEIGHT TO BE AT THE TOP OF THE ROOT BALL. NO ADDITIONAL FILL OR SOIL SHALL BE PLACED ON ROOT BALL.
 6. PROVIDE HOLE IN HOLDING AREA THAT IS THE SAME SIZE AS THE TREE ROOT BALL.
- E. TREE SUPPORTS
1. SUPPORT TREE WITH MACHINERY UNTIL BRACING IS COMPLETE.
 2. BUTTRESSES MAY SUPPORT SEPARATE TRUNKS ON MULTIPLE TRUNK TREES

3.04 IRRIGATION

- A. THE CONTRACTOR IS RESPONSIBLE FOR HAND WATERING ALL RELOCATED PLANT MATERIAL.

- B. DAILY WATERING AND MONITORING SHALL BE PERFORMED DURING THE TERM OF THE CONSTRUCTION CONTRACT AND UNTIL FINAL ACCEPTANCE.

- C. THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING WATER AT HIS/HER OWN EXPENSE.

- D. A TENSIONMETER SHALL BE UTILIZED TO MEASURE AND MONITOR AVAILABLE MOISTURE IN THE GROUND. WEEKLY OBSERVATION SHALL BE REPORTED IN ISA MEMBER'S REPORT.

3.05 PLANTING

- A. PLANTING AND BACKFILLING:
1. DIG PITS TO RECEIVE TRANSPLANTS WITH VERTICAL SIDES, FLAT BOTTOMS, SAME DEPTH AS THE TREE ROOT BALL, AND AT LEAST THREE TIMES LARGER THAN THE SIZE OF THE ROOT BALL.
 2. ALL PLANTING SOIL/SOIL BACKFILL TO BE USED IN PLANTING PITS SHALL BE AMENDED WITH AGRODIAMONDS, APPROVED EQUAL, NA (SODIUM) BASE SOIL POLYMER OR APPROVED EQUAL AT THE MANUFACTURERS RECOMMENDED APPLICATION METHODS AND RATES.
 3. PLANT TREE IN PIT AND ROTATE PRIOR TO SETTING TO ACHIEVE BEST POSITIONING RELATIVE TO ADJACENT TREES AND VIEWING ANGLES.
 4. ALL PLANT PITS AND BACK FILL MATERIAL MUST BE FREE OF ALL DEBRIS AND ROCKS IN EXCESS IF ½" IN DIAMETER.
 5. INSTALL TREE SO TOP OF ROOT BALL IS THREE-INCHES (3") WITH PROPOSED GRADE.
 6. FLOOD BOTTOM SOIL LAYER TO SETTLE TREE INTO BEST POSITION AND TO REMOVE AIR POCKETS.
 7. CONTINUE TO FLOOD ROOT BALL AS PLANTING SOIL MIX IS DEPOSITED TO REMOVE AIR POCKETS. MECHANICAL COMPACTION OF SOIL BACKFILL IS STRICTLY PROHIBITED.
 8. CONSTRUCT A 6" HIGH BERM AROUND THE OUTSIDE OF THE TREE PIT AFTER BACKFILLING TO RETAIN WATER.
- B. SOIL ADDITIVES
1. AGRODIAMONDS NA (SODIUM) OR APPROVED EQUAL BASE SOIL POLYMER SUPER ABSORBENT TO BE USED IN ALL RELOCATED PLANT MATERIAL AT THE MANUFACTURERS RECOMMENDED APPLICATION METHODS AND RATES.
 2. AGRODIAMONDS WITH A PARTICLE SIZE RANGE OF .5MM TO 2.8MM.

3.06 POST-RELOCATION GROW-IN PERIOD

- A. THE CONTRACTOR SHALL MAINTAIN ALL TRANSPLANTED MATERIAL IN A HEALTHY CONDITION UNTIL FINAL ACCEPTANCE.
- B. THE CONTRACTOR SHALL PREPARE ALL OPERATIONS NECESSARY TO ENSURE THAT PLANTS ARE HEALTHY, VIGOROUS, AND UNDAMAGED.
- 3.07 ACCEPTANCE**
- A. FOR THE PURPOSE OF ESTABLISHING AN "ACCEPTANCE" STANDARD, PLANTS SHALL BE HEALTHY AND EXHIBIT EVIDENCE OF ESTABLISHING NEW ROOTS.
1. PERFORM OPERATIONS AS NECESSARY TO COMPLETE MAINTENANCE AND ENSURE THAT PLANTS ARE HEALTHY, VIGOROUS, VISUALLY PLEASING, AND UNDAMAGED.
 2. PERFORM ALL MAINTENANCE TASKS AS SPECIFIED HERE IN.

- B. WHEN THE CONTRACTOR HAS MET THE OBLIGATIONS OF THE POST-TRANSPLANTING SCHEDULE, A SUBSTANTIAL COMPLETION INSPECTION SHALL BE CONDUCTED WITH ALL DEFICIENCIES NOTED AND GIVEN TO THE CONTRACTOR AS A PUNCH LIST OF ITEMS TO BE CORRECTED. FINAL ACCEPTANCE WILL NOT BE ISSUED UNTIL ALL PUNCH LIST ITEMS HAVE BEEN COMPLETED AND A RE-INSPECTION BY THE OWNER'S REPRESENTATIVE IS COMPLETED.

- C. AT THE CONCLUSION OF THE WARRANTY PERIOD, AN INSPECTION SHALL BE MADE TO DETERMINE THE CONDITION OF WARRANTED PLANT MATERIAL.
1. REMOVE ALL MATERIAL NOTED AS NOT BEING IN A HEALTHY-GROWING CONDITION.
 2. AT NO ADDITIONAL COST, REPLACE REJECTED MATERIAL WITH MATERIAL OF LIKE KIND AND SIZE, IN ACCORDANCE WITH THE SPECIFICATIONS.
 3. WARRANTY PERIOD APPLIES ALSO TO REPLACED MATERIAL.
 4. THE CONTRACTOR SHALL WARRANT ALL REPLACEMENT TREES FOR A PERIOD OF ONE (1) YEAR FROM THE DATE OF INSTALLATION.

3.08 GUARANTEE

- A. THE MINIMUM ALLOWABLE RATE OF SURVIVAL OF ALL TRANSPLANTED MATERIAL SHALL BE 100%. DEATH OF ANY RELOCATED PLANT MATERIAL SHALL BE REPLACED WITH THE SAME SIZE AND SPECIES. DETERMINATION OF SURVIVABILITY SHALL BE MADE AT THE END OF THE WARRANTY PERIOD.
- B. RELOCATED PLANT MATERIAL INSTALLED BY THE CONTRACTOR SHALL BE WARRANTED IN WRITING FOR A PERIOD OF ONE (1) YEAR FROM THE DATE OF FINAL ACCEPTANCE.



**ARCHITECTURE - INTERIOR
DESIGN - CIVIL ENGINEERING -
LANDSCAPE ARCHITECTURE :**

Bermello Ajamil & Partners, Inc.

Architecture Engineering Planning
Interior Design Landscape Architecture

2601 South Bayshore Drive, 10th Floor
Miami, Florida 33133

T: (305) 859-2050 F: (305) 860-3700

CLIENT:



**NOT FOR
CONSTRUCTION**

KIRK OLNEY FL LA LICENSE No.: 00001705

Revision Schedule		
Rev. #	Revision Description	Date

PROJECT NAME:
NORTH MIAMI BEACH
APARTMENTS

PROJECT ADDRESS:
NE 164TH ST & 19TH AVE,
NORTH MIAMI BEACH, FL 33162

PROJECT NO.:
02006

**P & Z AND CITY
COMMISSION
REVIEW**

12/10/2021

SHEET NAME
**TREE / PALM
PROTECTION AND
RELOCATION
SPECIFICATIONS**

SHEET NO.

LT-03

**NOT FOR
CONSTRUCTION**

KIRK OLNEY FL LA LICENSE No.: 00001705

Revision Schedule

Rev. #	Revision Description	Date
--------	----------------------	------

PROJECT NAME:
NORTH MIAMI BEACH
APARTMENTS

PROJECT ADDRESS:
NE 164TH ST & 19TH AVE,
NORTH MIAMI BEACH, FL 33162

PROJECT NO.:
02006


**P & Z AND CITY
COMMISSION
REVIEW**

12/10/2021

SHEET NAME
PERVIOUS /
IMPERVIOUS DIAGRAM

SHEET NO.

LA-00



PERVIOUS / IMPERVIOUS DATA


Zoning/Land Use:	MU/TC			
Net Lot Area:	81,163 S.F.			
Impervious area	79,710 S.F.			
Pervious area	1,453 S.F.			
PUBLICALLY ACCESSIBLE OPEN SPACE (PLAZA) 4,900 SQ FT	MINIMUM	MAXIMUM	PROVIDED	
Impervious surface: Minimum 50% - Maximum 75%	2,450 (50%)	3,675 (75%)	3,592(73.3%)	

LEGEND:	
	PLAZA BOUNDARY
	PERVIOUS / GREEN AREA
	IMPERVIOUS AREA

PLANT MATERIAL LEGEND		
QUANTITY	CANOPY AND ORNAMENTAL TREES	
6		EXISTING LIVE OAK TO REMAIN.
6		Quercus Virginiana - High Rise Live Oak 24' Height X 12" X 5" caliper; 8' clear trunk; Field Grown. Drought Tolerance: High
11		Bursera simaruba- Gumbo Limbo 18' Height X 10" X 5" caliper; 8' clear trunk; Field Grown. Drought Tolerance: High
QUANTITY	PALMS	
8		Veitchia montgomeryana - Montgomery Palm 25' to 30' Height; Staggered; Field Grown. Drought Tolerance: Moderate
1		Veitchia montgomeryana - Montgomery Palm Double 25' to 30' Height; Staggered; Field Grown. Drought Tolerance: High
5		Roystonea elata - Royal Palm 35' Height Overall; Matched; Field Grown. Drought Tolerance: High
1		Phoenix sylvestris - Triple Sylvester Date Palm 15' to 25' gray wood; Field Grown. Drought Tolerance: High

PLANT MATERIAL LEGEND		
QUANTITY	SHRUBS	
232		Ficus microcarpa 'Green Island' - Green Island Ficus 7 gallons; 24" X 24"; 24" O.C. Drought Tolerance: High
32		Nephrolepis biserrata - Macho Fern 3 gallons; 24" X 24"; 24" O.C. Drought Tolerance: Moderate
26		Acalypha wilkesiana - 'Java White' Copperleaf 7 gallons; 30" X 30"; 30" O.C. Drought Tolerance: Moderate
14		Diyon spinulosum - Gum Palm - 25 gallons; 5' X 5' Drought Tolerance: High
QUANTITY	GROUND COVERS	
305		Microsorium scolopendrium - Wart fern - 1 gallon; 10" X 10"; 18" O.C. Drought Tolerance: Moderate
66		Dianella tasmanica 'Variegata' - Variegated Flax Lily 3 gallons; 18" X 18"; 24" O.C. Drought Tolerance: Moderate
58		Emodia littoralis - Golden Creeper - 1 gallon; 12" X 12"; 24" O.C. Drought Tolerance: High


GROUND FLOOR FURNITURE LEGEND		
QTY.	SYMBOL	DESCRIPTION
2		BACKLESS BENCH (75" L X 22.7" W)
2		BACKED BENCH (74.8" LX 20.1" W)
23		TREE GRATE (8' L X 4' W) ALL TREE GRATES TO BE ADA COMPLIANT
5		LITTER RECEPTACLE (45.3 H X 26.8" W)
14		EXISTING LIGHT TO REMAIN
30		BOLLARDS
NOTE: FURNITURE SPECIFICATIONS ARE SUBJECT TO CHANGE PER CITY'S REQUIREMENTS AT THE TIME OF BUILDING DEPARTMENT PERMITTING		





SITE DATA			
Zoning/Land Use:	MU/TC		
Net Lot Area:	81,163 SF		
Open Space	20,657 SF		
LANDSCAPE REQUIREMENTS & CALCULATIONS			
URBAN GREENWAY TYPE 2 (UG-2): NE 19TH AVENUE	CALCULATION	MINIMUM	PROVIDED
Minimum width of greenway	N/A	24' LF	26'-6" LF
TREES	CALCULATION	REQUIRED	PROVIDED
Perimeter Trees provided at average maximum spacing of 30' O.C.			
LF of property line along 164th Street 561' (6 Existing + 6 Proposed)	561' / 30'=	19	12*
LF of property line along 19th Avenue 162' 6 Trees + 5 Palms at 3:1	162' / 30'=	6	7
LF of property line along 20th Avenue 140' (5 Trees + 4 Palms at 3:1)	140' / 30'=	5	6
TOTAL PERIMETER TREES		30	25
Motor Court Trees	N/A	N/A	5
TOTAL TREES		30	30
PALMS	CALCULATION	MAXIMUM	PROVIDED
Maximum 25% of all required trees to be palms (9 Palms at 3:1)	30 X .25=	7	3
PUBLICALLY ACCESSIBLE OPEN SPACE	MINIMUM	MAXIMUM	PROVIDED
Plaza	4880 SF	N/A	4900 SF



* Existing force main line along N.E. 164th Street limits the possibility of having all the required street trees
Mitigation trees will be provided off site at a location agreed upon with the city staff.

URBAN GREENWAY				
LENGTHEN OF URBAN GREENWAY	No. OF TREES	CANOPY	LENGTH OF SHADE	% OF SHADE
120'	6	10'	6 X 10'=60'	60 / 70 = 86%






3	AMENITY DECK LANDSCAPE AND FURNITURE LEGEND
LA-02	SCALE: N/A




SHEET NO.

A-02



1 GROUND FLOOR FURNITURE IMAGES
LA-03 SCALE: N/A



2 AMENITY DECK FURNITURE IMAGES
LA-03 SCALE: N/A